


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by Frank W. Campbell under GLO contract number 468, dated 1883. Surveyor General record states: Set basalt stone 18x11x9 ins 12 ins in ground for 1/4 sec cor marked 1/4 on W face; from which:  
 A pine 18 ins dia brs N72°W 54 lks. dist. marked 1/4 S BT  
 A pine 30 ins dia brs N79°E 4 lks. dist. marked 1/4 S BT  
 Corner remonumented by BLM in 1978. BLM notes state: The 1/4 sec cor of secs 23 and 24, monumented with the original unmarked basalt stone, 18x11x9 ins, firmly set 10 ins in the ground from which the remains of the original bearing trees:  
 A pine snag 15 ins diam bears N79°E 4 lks dist with scribes visible on open blaze. A decayed pine stump bears N72°W 54 lks dist with no marks visible. At the corner point:  
 Set an iron post 28 ins long 2 1/2 ins diam 22 ins in the ground and in a mound of stone 3 ft. base to top with brass cap marked (shown below) from which new bearing trees:  
 A white fir 16 ins diam bears S43°E, 5 lks dist mkd 1/4 S24 BT. A white fir 14 ins diam bears N69°W, 75 lks dist mkd 1/4 S23 BT. Deposit corner stone alongside iron post.




No record of subsequent monumentation found in Umatilla County survey records.

Description of corner evidence found:

Found a 2 1/2" standard BLM brass cap monument marked as shown in mound of stone.

Found original Northeast bearing tree and BLM bearing trees as described in the BLM record above. Blazes on BLM trees have healed over. (Did not identify original Northwest bearing tree)

Distances to existing BTs are to the center of the tree



Description of monument and accessories I established to perpetuate the original location of this corner:

Painted a 6 inch red band around all BTs and attached bearing tree and land survey monument signs, except original Northwest bearing tree stump, which was not identified.

Set a steel fencepost approximately 5 feet North with land survey monument and property boundary sign attached.

I hereby certify that the above corner point was perpetuated as hereon described on May 6, 1989.

Witnesses: Rick Robinson and Jeff Petersen.



Office of Surveyor County of Umatilla  
 State of OR, I hereby certify that the within instrument was filed in this office for record on the 28<sup>th</sup> day of June, 1989  
David H. Lumbert by Katherine K. Ambrose  
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY  
 Umatilla County Surveyor  
 Date 6-89  
 Filed KA  
 No. 89-60-R

☆ U.S. GOVERNMENT PRINTING OFFICE - 1983-793-276