

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


2-1

History of original corner establishment:

George S. Pershin under Contract No. 362 dated August 2, 1880:

Set Basalt Stone 18 X 12 X 8 from which

Pine, 18" Dia., BRS. N52°W, 80 Lks. Dist.
Pine, 12" Dia., BRS. S50°E, 54 Lks. Dist.



Description of corner evidence found:

Found (BRG. and DIST. from re-established corner point; original stone is now gone).

Ponderosa Pine, 28" Dia., BRS S50°E., 35.6 Ft. Dist. with scribing visible on open blaze.

Description of monument and accessories established to perpetuate the original location of this corner

Set 32" X 2" flanged iron pipe with brass cap marked:
From which new BTs

SC
T5S R30E
1/4 S32
1979
PLS 346

Douglas Fir, 12" Dia., BRS. N10°W., 14.7 Ft. Dist.
Marked: 1/4 S32 SC BT
Douglas Fir, 8" Dia., BRS. N58 1/2°E., 14.8 Ft. Dist.
Marked: 1/4 S32 SC BT
6" iron fence post with "Attention" sign within 5' of corner.


All B.T. have BT tag and painted red stripe. New BTs have brass washer stamped: PLS 346; nailed to lower blaze.

Office of _____ County Surveyor _____ County of Umatilla _____
State of Oregon _____, I hereby certify that the within instrument was filed in this office
for record on the _____ day of _____

(COUNTY OFFICIAL) by _____ (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor
Date 10-17-79
Rec'd By MJ
No. Q-1171-B



GPO 796-332

2-1