

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 08/28/02

CORNER DESIGNATION: G-21, The East 1/4 Corner of Section 11, T5S, R31E, W. M.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by George S. Pershin, under Contract No. 373, dated September 17, 1880. Notes state: Set post for 1/4 Section corner on level. A pine, 10 ins. diam., brs. N 40° E., 7 lks. dist. A pine, 10 ins. diam., brs. N 45° W., 7 lks. dist.

MONUMENT AND ACCESSORIES FOUND: Found a stump hole and a 6" high pitched stump stub as remaining evidence of original bearing trees. The bearing and distance between these fit the record. The corner position was determined by distance-distance intersection from these two found accessories, using record distances.

MONUMENT MARKING DETAIL:

T5S R31E
1/4
S11 | S12
2002
PLS 1106

MONUMENT SET:

At position determined by record distance-distance intersection from bearing tree remains, set a 2 1/2" brass cap on a 1 1/4" x 30" galvanized iron pipe with top flush with ground level. Monument marked as shown in "Monument Marking Detail".

New Accessories:

A 10" diam. ponderosa pine scribed "1/4 S12 BT" with a 3/4" brass washer stamped "PLS1106" nailed to face of blaze bears N 61° E, 46.6 feet.

A 14" diam. ponderosa pine scribed "1/4 S12 BT" with a 3/4" brass washer stamped "PLS1106" nailed to face of blaze bears S 50° E, 74.6 feet.

A 12" diam. ponderosa pine scribed "1/4 S11 BT" with a 3/4" brass washer stamped "PLS1106" nailed to face of blaze bears S 31° W, 114.5 feet.

A 14" diam. ponderosa pine scribed "1/4 S11 BT" with a 3/4" brass washer stamped "PLS1106" nailed to face of blaze bears N 69° W, 96.9 feet.

Attached bearing object signs to new accessories. Attached witness sign to steel fence post 1 foot North of monument.

LOCATION AND COMMENTS:

Corner falls in a lightly treed area 30 feet west of a fence running North and South.

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Mark Hammersla

\SS31G21

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will. R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-04
RECEIVED BY

Umatilla County Surveyor

Date 10-02

Rec'd By KK

No. 02-218-B