


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

J-25

History of original corner establishment: Corner established in 1880 by George S. Pershin under General Land Office Contract No. 373.



Surveyor General Records States:

Set basalt stone 17 x 8 x 7 ins. for cor. to sect's 7-18-12-13.

- A 12" Pine bears N 56 E, 167 lks.
- a 10" Pine bears S 42 E, 28 lks.
- A 26" Pine bears S 38 W, 116 lks.
- A 28" Pine bears N 62 W, 210 lks.

No record of subsequent remonumentation was found in County Records.

Description of corner evidence found:
Found mound of stone, from which:

Original BTs

- A 18" Pine, good condition, bears S39E, 18.5 ft., blaze healed. North-South fence attached to this tree.
- A 27" Pine, good condition, bears S42W, 76.6 ft., scribes visable.

No evidence of other BTs and could not identify original marked stone.

Description of monument and accessories I established to perpetuate the original location of this corner

At corner point, based on original BTs, I set 2 1/2"x30" iron pipe with brass cap, marked as shown, 24" in ground, from which:


New BTs

- A 14" Pine bears N78E, 45.1 ft. marked T5S R31E S7 BT.
- A 10" Pine bears N28W, 31.3 ft. marked T5S R30E S12 BT.

Nailed brass washer to BT blaze.
 Set steel fence post 5+ ft. East of corner
 Raised mound of stone 5 ft. at base to top of cap.
 Used steel tape and magnetic compass with 20° E declination.
 Measured to face of blaze on original BTs and center of new BTs.

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

Handwritten Signature
 OREGON
 JULY 10, 1924
 DUANE J. GRIFFITH
 644



Office of Surveyor County of Umatilla
 State of Oregon, I hereby certify that the within instrument was filed in this office
 for record on the 13 day of Aug, 1974 at 11 o'clock am, (signed)
Ralph Thompson by _____ (DEPUTY)

J-25