


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T-2

History of original corner establishment:

None

Index No. T-2



No record of subsequent remonumentation found in County Records .  
Description of corner evidence found:

None

Description of monument and accessories established to perpetuate the original location of this corner

At the corner position a 2 inch by 30 inch iron pipe, with brass cap marked as shown, was set 15 inches in the ground and surrounded with a mound of stones to the cap .

Set steel fence post on line North of corner and attached signs 54-2 and 54-9.

Set 2 New BT's:

6" Red Fir Bears S84°E 40.5 ft scribed CW 1/16 530 BT

8" Red Fir Bears S 19°W 12.7 ft. scribed CW 1/16 530 BT.

BT's have lower blaze scribed BT with a brass washer stamped PLS 1106 nailed to it.

BT's have 54-3 and 54-4 signs attached and a 6" red band painted around them above blaze.

Used steel tape and magnetic compass with 19½° east declination . Measured to center of Bts.

See map of survey


This corner set August 27, 1979

Witnesses: Greg Flowers L.S.I.T.  
Brent Reynolds

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106



Office of County Surveyor County of Umatilla  
State of Oregon , I hereby certify that the within instrument was filed in this office  
for record on the ..... day of .....  
..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

**RECEIVED BY**

Umatilla County Surveyor

Date Sept 4, 1979

Rec'd By M. Hughes

No. Q-1164-B

Form R6-7100-57 (9/71)

Note: This corner was established in error in 7/79 and bearing trees established. When the corner was established in its true position, scribing and signs were removed from the BT's referencing the erroneous position  
From the correct corner position: A 8½" red fir bears N 16½°E 50.5 ft with open blaze  
A 8" bullpine bears S35½°E 42.3 ft with open blaze