


History of original corner establishment:

None

Index No. T-3



No record of subsequent remonumentation found in County Records .  
Description of corner evidence found:

None

Description of monument and accessories I established to perpetuate the original location of this corner

At the corner position a 2 inch by 30 inch iron pipe, with brass cap marked as shown, was set 24 inches in the ground and surrounded with a mound of stones to the cap .

Set steel fence post on property line North of corner and attached signs 54-2 and 54-9.

Established two (2) new BT's: A 8 " red fir bears S65°E 9.7 ft. scribed C 1/4 S 30 BT.

A 10" red fir bears S8°E 17.1 ft. scribed C 1/4 S 30 BT.

BT's have a lower blaze scribed BT with a brass washer stamped PLS 1106 nailed to it.

BT's have 54-3 and 54-4 signs attached and a 6" red band painted around them above blaze.

Used steel tape and magnetic compass with 19 1/2° east declination . Measured to center of Bts.  
See map of survey

This corner set August 21, 1979

Witnesses: Greg Flowers, L.S.I.T.  
Brent Reynolds

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

T55 R31E  
C 1/4 S30  
1979  
PLS 1106

Office of County Surveyor County of Umatilla  
State of Oregon , I hereby certify that the within Instrument was filed in this office  
for record on the ..... day of .....  
..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY  
Umatilla County Surveyor  
Date Sept 4, 1979  
Rec'd By M Hughes  
No. Q-1164-B

Form R6-7100-57 (9/71)

NOTE: This corner was erroneously established in 7/79 and bearing trees established when the corner was established in its true position, scribing and signs were removed from BT's referencing the erroneous position. From the correct corner position: A 13" red fir bears N 68 1/2°E 177'+w/open blazes.  
A 11 1/2 " red fir bears N85°E 156'+w/open blazes.