


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index No. U-4

History of original corner establishment:

None



No record of subsequent remonumentation found in County Records .  
Description of corner evidence found:

None

Description of monument and accessories established to perpetuate the original location of this corner

At the corner position a 2 inch by 30 inch iron pipe, with brass cap marked as shown, was set 18 inches in the ground and surrounded with a mound of stones to the cap .  
Set steel fence post North and West of corner and attached signs 54-2 and 54-9.  
Established 2 new BT's: A 14 1/2" bull pine bears N 16 1/2° W 39.8 ft. scribed SE 1/16 S 30 BT.  
A 21" bull pine bears N20° E 62.2 ft. scribed SE 1/16 S 30 BT.  
BT's have 54-3 and 54-4 signs attached and a 6" red band painted around them above blaze.

Used steel tape and magnetic compass with 19 1/2° east declination . Measured to center of Bts.  
See map of survey


This corner set August 20, 1979

Witnesses: Greg Flowers, L.S.I.T.  
Brent Reynolds

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106



Office of County Surveyor County of Umatilla  
State of Oregon , I hereby certify that the within instrument was filed in this office  
for record on the ..... day of .....  
..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Surveyor

Date Sept 4 1979

Rec'd By M. Skyles

No. Q-1164-B