

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 08/29/02

CORNER DESIGNATION: G-25, The East 1/4 Corner of Section 12, T5S, R31E, W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by George S. Pershin, under Contract No. 362, dated August 2, 1880. Notes state: Set basalt stone 18 x 10 x 8 in mound of stone on level prairie for 1/4 Sec. Cor..

MONUMENT AND ACCESSORIES FOUND: Found a 18" x 10" x 8" stone marked 1/4 laying in a rock crib with fences North and N 79° W. Accepted Southeast corner of rock crib as best remaining evidence of the original corner after verifying corner location with sub-meter GPS relative to recovered Southeast Corner of Section 12.

**MONUMENT MARKING DETAIL:**

T5S  
R31E R32E  
1/4  
S12 | S7  
2002  
PLS 1106

**MONUMENT SET:**

At the Southeast corner of rock crib, set a 2 1/2" brass cap on a 1 1/4" x 30" galvanized iron pipe with cap 4" above ground level. Monument marked as shown in "Monument Marking Detail". Buried original stone on Southeast side of new brass cap monument with top 4" above ground level.

**New Accessories:**

A 3/4" Brass washer stamped "PLS 1106" 1.0 feet above ground nailed to a rock jack fence post bears North, 41.4 feet.

A 34" diam. ponderosa pine scribed "1/4 S7 BT" with 3/4" brass washer stamped "PLS 1106" nailed to face of blaze bears N 87° E, 194.5 feet.

A 22" diam. ponderosa pine scribed "1/4 S12 BT" with 3/4" Brass washer stamped "PLS 1106" nailed to face of blaze bears S 57° W, 220.2 feet.

A brass washer stamped "PLS 1106", 1.0 feet above ground level nailed to a rock jack fence post bears N 79° W, 49.3 feet.

Attached bearing object signs to new accessories. Attached witness sign to rock crib immediately Northwest of corner monument.

**LOCATION AND COMMENTS:**

Corner falls in a open area 0.5 feet Southeast of a rock crib with fences North and N 79° W.

FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT  
Mark Hammersla  
\\SS31G25

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Will. R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-04*

RECEIVED BY

Umatilla County Surveyor

Date 10-02

Rec'd By KE

No. 02-218-B