

USDA-FOREST SERVICE

Index

File No. 2-14

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or
Survey No. _____

Cor.
No. W 1/2

T 43 R. 33E

R.D. Ukiah County Umatilla

Merid. Willamette

N.F. Umatilla State Oregon

CORNER DIAGRAM

T43R33E



W 1/2 534
53

DESCRIBE CORNER MONUMENT FOUND

None

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None

PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At. _____

Object Ident. _____

Ident. By _____

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From jet of Ukiah - Hilgard Highway and Forest Road 54 go South 0.2 mi., park and walk East 300 feet to corner.

Signature

David H Klein

Title

P.L.S. 933

Division


Headquarters

Date 7-1983 7100-52 (3-68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 2 1/2" dia. Brass Cap on a 2 1/2" dia. x 30" galvanized pipe set
22" in ground marked:



ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A 6" dia. pine bears S44°W, 82.0 feet scribed T5S R33E 1/6 S3 BT
A 8" dia. pine bears N88°30'E, 135.6 feet scribed T4S R33E 1/6 S34 BT
Blazes are painted red, Trees have a red band painted around them.
Trees have sign numbers 54-3, 54-9, + Brass Washers stamped PLS.
933 nailed to them.

Work Done By D. Krumbain Title Surveyor Date 7-1983 State Registration No. or Agency PLS 933

Certified Cor. Record Prepared? (Yes) No Filed At: Umatilla County Date 7-1983

REMARKS

Index File No. 2-14 T. 4S R. 33E M. Willamette Tract or Surv. No. Cor. W 1/6