


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

B-15

**History of original corner establishment:**

This corner was monumented by Duane Griffith, PLS 644, during a survey in Section 3 in 1975. He set a 2½"x30" iron pipe with a brass cap marked:

T5S R33E  
CN 1/16  
S3  
1975  
PLS 644



**From which:**

A Lodgepole, 9" dia., N17°W, 6.2 ft.  
A Lodgepole, 8" dia., S25°W, 24.7 ft.

**Description of corner evidence found:**

Found a 2½" iron pipe with a brass cap marked according to the record  
From which:

A Lodgepole, 8" dia., dead and down, with scribing visible,  
the stump of which bears N21°W, 6.2 ft.  
A Lodgepole, 7" dia., dead and down, with scribing visible,  
the root hole of which bears S23°W, 24.7 ft.

**Description of monument and accessories I established to perpetuate the original location of this corner:**

**Mark new BTs:**

A Tamarack, 9" dia., S21½°E, 67.0 ft. marked: CN 1/16 S3 BT  
A Tamarack, 7" dia., S49°W, 117.0 ft. marked: CN 1/16 S3 BT

BTs have blazes and a 6" stripe painted red, a BT tag and a "Land Survey Monument" sign. New BTs have, additionally, an alum. "PLS 1832" washer nailed to the bottom of the blaze. There is a 6' steel fence post with a "Land Survey Monument" sign within 5' of the corner.

Measured to center of BTs using steel tape and staff compass. Magnetic declination set at 16°E.

September 16, 1984.



Office of Surveyor County of Umatilla  
State of Oregon, I hereby certify that the within instrument was filed in this office  
for record on the 10 day of October, 1984  
David H. Krumben by \_\_\_\_\_  
(COUNTY OFFICIAL) (DEPUTY)