


History of original corner establishment:

Corner not set in 1881 by George S. Pershin under General Land Office Contract No. 430.

None.




No record of subsequent remonumentation was found in county records.  
Description of corner evidence found:

( See map of survey, dated December 1975 )

Description of monument and accessories established to perpetuate the original location of this corner

At corner position I set 2 1/2" X 30" iron pipe with brass cap marked as shown 27" in ground, from which:  
A 9" Lodgepole Pine bears N 17° W, 6.2 ft. marked C-N 1/16 S 3 BT.  
A 8" Lodgepole Pine bears S 25° W, 24.7 ft. marked X BT.  
Set steel fence posts 5+ ft. East and North



REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Duane I. Griffith*

OREGON  
JULY 10, 1904  
DUANE I. GRIFFITH  
644

Brass Washer nailed to BT blazes.  
Used steel tape and magnetic compass  
with 19° 30' East declination.  
Measured to center of all BTs.

Office of..... County of.....  
State of....., I hereby certify that the within instrument was filed in this office  
for record on the..... day of.....  
..... by .....

(COUNTY OFFICIAL)

(DEPUTY)

B-15

Q-901

33