


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established in 1882 by George S. Pershin  
under General Land Office Contract No. 430.  
Surveyor General Records state:

Set basalt stone 18 X 12 X 7 ins. for 1/4 sec.cor.  
from which:

- A Tamarack 13 in. dia. brs. N 85° E, 37 lks. dist.
- A Fir 18 in. dia. brs. N 20° W, 16 lks. dist.



Nor record of subsequent remonumentation was found in county records.  
Description of corner evidence found:

Found stone marked 1/4 in mound of stone from which:  
A 18" Tamarack bears N 84° E, 26.4 ft. blazes closed.  
A 20+ " Fir, dead and down, badly rotted bears N 25° W, 6+ ft.  
BT Visible.


( See map of Survey, dated December, 1975 )

Description of monument and accessories I established to perpetuate the  
original location of this corner

In place of stone I set 2 1/2" X 30" iron pipe with brass cap marked  
as shown 25" in ground, from which:

New BT:

- A 12" Tamarack bears N 52° W, 16.6 ft. marked 1/4 S4 BT.
- Buried stone East and along side pipe.
- Raised mound of stone 3 ft. base to top of cap.
- Set steel fence post 5+ ft. South.



REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Handwritten Signature*

OREGON  
JULY 10, 1994  
DUANE J. GRIFFITH  
644

Brass Washer nailed to BT blazes.  
Used steel tape and magnetic compass  
with 19° 30' East declination.  
Measured to center of all BTs.

Office of..... County of.....  
 State of....., I hereby certify that the within instrument was filed in this office  
 for record on the ..... day of.....  
 ..... by .....  
 (COUNTY OFFICIAL) (DEPUTY)

C-13