


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

C-18

History of original corner establishment:

No record of previous monumentation.



Description of corner evidence found:

None.

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2½"x30" alum. pipe with a 3" alum. cap containing a magnet and marked:

From the corner:

A Lodgepole, 10" dia., S3°W, 42.0 ft. marked: CW 1/16 S2 BT
A Lodgepole, 7" dia., S72°W, 59.6 ft. marked: CW 1/16 S2 BT

W 1/16
C—C
PLS 1832
1984

BTs have blaze and a 6" stripe painted red, a BT tag, a "Land Survey Monument" sign and an alum. "PLS 1832" washer nailed to the bottom of the blaze. There is a 6' steel fence post with a "Land Survey Monument" sign within 5' of the corner.

Measured to center of BTs using steel tape and staff compass. Magnetic declination set at 16½°E.

September 15, 1984.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Fayette S. Munro
OREGON
JULY 13, 1979
FAYETTE S. MUNRO
1832

Office of Surveyor County of Umatilla
State of Oregon. I hereby certify that the within instrument was filed in this office
for record on the 10 day of October 1984
David H. Krumbain by [Signature]
(COUNTY OFFICIAL) (DEPUTY)

B4-132-R