

USDA-FOREST SERVICE

Index File No. C-22

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. \_\_\_\_\_ Cor. No. CW 1/16


T 5S R. 33 E

R.D. Ukiah County Umatilla

Merid. Willamette

N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

None Set

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None Set

PHOTO IDENTIFICATION DATA

Photo No. \_\_\_\_\_

Filed At. \_\_\_\_\_

Object Ident. \_\_\_\_\_

Ident. By \_\_\_\_\_

*Signature*

PLANE COORDINATE POSITION DATA

State \_\_\_\_\_ Zone \_\_\_\_\_

X \_\_\_\_\_

Y \_\_\_\_\_

Estab. By \_\_\_\_\_

*Agency*

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner falls in large open glade 60 ft north and 6 ft west of N-W fence corner.

Title

Division

Headquarters

Date

7100-52-(3/68)

*Signature*

ORLS

1224

9-77

**CORNER RECORD (PERPETUATION)**

**MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT**

At surveyed point set 2 1/2"X30" galvanized pipe with  
brass cap stamped:  
Set pipe 24" in ground with mound of stone to cap.

T5S R33E

W 1  
T6

C — | — C

S1

1980

OR PLS 1294

9

**ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE**

Bearing Trees:

A Lodge Pole Pine 14" dia bears S74<sup>0</sup>E, 73.0 ft., scribed CW1/16 S1 BT.

A Lodge Pole Pine 5" dia bears S1<sup>0</sup>W, 73.6 ft., scribed CW1/16 S1 BT.

Attached 54-3 & 54-4 signs to both BTs. Attached brass washer stamped LS 1294 to foot blaze of both BTs. Painted blazes and 6" band around both BTs Red. Attached 54-2 & 54-4 signs to metal post 5 ft north of corner. Attached 54-2 & 54-9 signs to metal post 5 ft west of corner.

10

Work Done By R. C. Orton Title Party Chief Date 6-19-80 State Registration No.                       
or Agency                     

Certified Cor. Record Prepared? (Yes)      No      Filed At:                      Date                      11

**REMARKS**

Witnesses: R. Orton  
              G. Orton  
              D. Allen