

USDA-FOREST SERVICE


Index
File No. C-23
T 5S R. 33E
Merid. Willamette

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

R.D. Ukiah County Umatilla Tract or Survey No. _____ Cor. No. C $\frac{1}{4}$
N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

No corner was originally set.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None set.

PHOTO IDENTIFICATION DATA

Photo No. _____
Filed At. _____
Object Ident. _____
Ident. By _____
Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner falls on North slope approximately 500 ft. East of paved road to Lehman Springs.

PLANE COORDINATE POSITION DATA

State _____ Zone _____
X _____
Y _____
Estab. By _____

Agency
Signature
Howard D. Reed

Title _____ Division ORLS Headquarters 1294 Date 9/77 7100-52-(3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

At surveyed point set 2½"x30" galvanized pipe with brass cap stamped:

Set pipe 22" in ground with mound of stone to cap.

T5S R33
C¼ | S1

1980
OR PLS 1294

9

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

Bearing Trees:

A Lodgepole Pine 7" dia., bears N25°E, 71.4 ft., scribed C¼ S1 BT.

A Ponderosa Pine 10" dia., bears S82°W, 67.6 ft., scribed C¼ S1 BT.

Attached 54-3 and 54-4 signs to both BTs. Attached brass washer stamped LS 1294 to foot blaze of both BTs. Painted blazes and 6" band around both BTs RED. Attached 54-2 and 54-4 signs to metal post 6 ft. East of corner. Attached 54-2 and 54-9 signs to metal post 6 ft. North of corner.

10

Work Done By: R. C. Orton Title Party Chief Date 6/13/80 State Registration No. or Agency _____

Certified Cor. Record Prepared? Yes No Filed At: _____ Date _____ 11

REMARKS

Witnesses: R. Orton
G. Orton
D. Allen