


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

No record of previous monumentation.



Description of corner evidence found:

None.

Description of monument and accessories | established to perpetuate the original location of this corner:

Set a 2½"x30" alum. pipe with a 3" alum. cap containing a magnet and marked:

SW 1/16 S2
PLS 1832
1984

Built a stone mound around the monument.

From the corner:

A P. Pine, 10" dia., N63½°E, 46.2 ft. marked: SW 1/16 S2 BT

A P. Pine, 10" dia., S61½°E, 61.9 ft. marked: SW 1/16 S2 BT

BTs have blaze and a 6" stripe painted red, a BT tag, a "Land Survey Monument" sign and an alum. "PLS 1832" washer nailed to the bottom of the blaze. There is a 6' steel fence post with a "Land Survey Monument" sign within 5' of the corner.

Measured to center of BTs using steel tape and staff compass. Magnetic declination set at 17 3/4°E.

September 15, 1984.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

Fayette S. Munro

OREGON
JULY 13, 1979
FAYETTE S. MUNRO
1832

Office of... Surveyor County of Umatilla

State of Oregon I hereby certify that the within instrument was filed in this office
for record on the 10 day of October 1984

David H. Keumbein by
(COUNTY OFFICIAL) (DEPUTY)