


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. D-23

History of original corner establishment:  
No corner was originally set.



Description of corner evidence found:

Description of monument and accessories I established to perpetuate the original location of this corner:


At surveyed point set 2 1/2"x30" galvanized pipe with brass cap stamped:

Set pipe 24" in ground with mound of stone to cap.

Bearing Trees:

A Tamarack 5" dia., bears S64°E, 31.3 ft., scribed CS 1/16 S1 BT.

A Tamarack 7" dia., bears N60°E, 16.4 ft., scribed CS 1/16 S1 BT.



Attached 54-3 and 54-4 signs to both BTs. Attached brass washer stamped LS 1294 to foot blaze of both BTs. Painted blazes and 6" band around both BTs Red. Attached 54-2 and 54-4 signs to metal post 6 ft. East of corner. Attached 54-2 and 54-9 signs to wood post 12 ft. South of corner.

I hereby certify the above corner monument was established as herein described on June 18, 1980.

Witnesses: R. Orton  
G. Orton  
D. Allen



Office of..... County Surveyor..... County of..... Umatilla.....  
 State of..... Oregon....., I hereby certify that the within instrument was filed in this office  
 for record on the..... day of..... December....., 1980.  
 ..... Dave Kousmin..... by..... Betty Shatto.....  
 (COUNTY OFFICIAL) (DEPUTY)