


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established in 1882 by George S. Pershin under General Land Office Contract No. 430. Surveyor General Records state:

Set basalt stone 17 X 10 X 8 ins. in mound of stone for cor. to secs 2,3,10,11 from which:
 A Pine 12 ins. dia. brs. N 58° E, 86 lks. dist.
 A Pine 10 ins. dia. brs. S 60° E, 54 lks. dist.
 A Pine 9 ins. dia. brs. S 4° W, 42 lks. dist.
 No tree in NW.



Nor record of subsequent remonumentation was found in county records.


Description of corner evidence found:

Found stone 17" X 10" X 8" with marks in mound of stone, from which:
 Original BT:
 A 14" Pine, dead and down bears N 63° E, 57.2 ft. scribes visible.
 A 18" Pine, vigorous bears S 66° E, 35.5 ft. blaze evident.
 A 14" Pine, vigorous bears S 11° W, 28.6 ft. scribes visible.

(See map of Survey, dated December, 1975)

Description of monument and accessories established to perpetuate the original location of this corner

At corner position I set 2 1/2" X 30" iron pipe with brass cap marked as shown 20" in ground, from which:
 New BTs:
 A 9" Pine bears N 63° E, 52.9 ft. marked T5S R33E S2 BT.
 A 8" Fir bears N 88° W, 6.7 ft. marked T5S R33E S3 BT.
 Buried stone East and along side pipe.
 Raised mound of stone 5 ft. base to top of cap.
 Set steel fence post 3 + ft. North



Brass Washer nailed to BT blazes.
 Used steel tape and magnetic compass with 19° 30' East declination.
 Measured to center of all BTs.

Office of..... County of.....
 State of....., I hereby certify that the within instrument was filed in this office for record on the day of

..... by

(COUNTY OFFICIAL) (DEPUTY)