


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. H-24

History of original corner establishment:

No corner was originally set.




Description of corner evidence found:

Description of monument and accessories I established to perpetuate the

original location of this corner: At surveyed point set
2 1/2"X30" galvanized pipe with brass cap stamped:

Set pipe 24" in ground with mound of stone to cap.



Bearing Trees:

A Lodge Pole Pine 8" dia bears N45°E, 26.2 ft., scribed SE1/16 S12 BT.

A Tamarack 18" dia bears S24°W, 47.0 ft., scribed SE1/16 S12 BT.

Attached 54-3 & 54-4 signs to both BTs. Attached brass washer stamped LS 1294 to foot blaze of both BTs. Painted blazes and 6" band around both BTs Red. Attached 54-2 & 54-4 signs to metal post 5 ft west of corner. Attached 54-2 & 54-9 to metal post 5 ft south of corner.

I hereby certify the above corner monument was established as herein described on July 8, 1980.

Witnesses: R. Orton
L. Huntsman
D. Allen



Office of.....County Surveyor..... County of.....Umatilla.....
 State of.....Oregon....., I hereby certify that the within instrument was filed in this office
 for record on the.....day of.....December....., 1980
David A. Brumbach..... by.....Betty Skatts.....
 (COUNTY OFFICIAL) (DEPUTY)

R-187-B