


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. J-24

History of original corner establishment:

No corner was originally set.



Description of corner evidence found:

Description of monument and accessories I established to perpetuate the

original location of this corner: At surveyed point set
2 1/2"X30" galvanized pipe with brass cap stamped:
Set pipe 24" in ground with mound of stone to cap.

T5S R33E
E $\frac{1}{16}$ $\frac{S12}{S13}$
1980
OR PLS 1294

Bearing Trees:

A Douglas Fir 8" dia bears N42°E, 12.5 ft., scribed E1/16 S12 BT.
A White Fir 9" dia bears S83°W, 19.5 ft., scribed E1/16 S13 BT.

Attached 54-3 & 54-4 signs to both BTs. Attached brass washer stamped
LS 1294 to foot blaze of both BTs. Painted blazes and 6" band around
both BTs Red. Attached 54-2, 54-4 & 54-9 signs to metal post 5 ft north
of corner.

I hereby certify the above corner monument
was established as herein described on
July 8, 1980.

Witnesses: R. Orton
L. Huntsman
D. Allen



Office of.....County..Surveyor..... County of.....Umatilla.....
Oregon....., I hereby certify that the within instrument was filed in this office
for record on the..... day of.....December....., 19⁸⁰.....
David Krumbein..... by *R. Hutto*.....
(COUNTY OFFICIAL) (DEPUTY)