


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

P-5

History of original corner establishment:

Corner was established by George S. Pershin in 1882 under contract # 430  
Set was a Basalt Stone ;7" x 10" x 5", 12" in the ground marked "1/4" on West side  
A mound of stone was raised along side



Description of corner evidence found:

None

Description of monument and accessories I established to perpetuate the original location of this corner By Proportionate Method

Set a 2 1/2" dia. Brass Cap on a 2 1/2" x 30" galvanized pipe 15" in the ground and a mound of stones around the Brass Cap, which is stamped as shown:

From which I scribed the Bearing Trees

A 12" dia. Ponderosa Pine bears N 48° E, 15.9 feet scribed 1/4 S 20 BT

A 8" dia. Ponderosa Pine bears N 39° W, 25.1 feet scribed 1/4 S 19 BT

Bearing trees have: A Brass Washer stamped PLS 933 nailed to the BT scribe, a painted band around the tree and on the face of the scribe, signs # 54-3 & 54-4

Bearing trees were measured horizontally with a steel tape to the center of the tree and a magnetic compass with a 19° East variation.

Also set a steel fence post with sign # 54-4 by Brass Cap Aug. 6, 1984

Witness: R. PUNCHES  
S. CARLSON



REGISTERED PROFESSIONAL LAND SURVEYOR

David H Klein  
OREGON  
JULY 17, 1970  
DAVID H. KRUMBEIN  
933

Office of Surveyor County of Umatilla  
State of Oregon, I hereby certify that the within instrument was filed in this office for record on the 21st day of November, 1984  
by Betty Cochran (DEPUTY)  
(COUNTY OFFICIAL)