

USDA-FOREST SERVICE

Index

File No. T-5

T 58 R. 33E

Merid. W.M.

CORNER RECORD (SEARCH)

N. Fk. (Ref. FSM 7151.4)

Tract or

Survey No. _____

Cor.

No. _____

R.D. John Day County Umatilla

N.F. Umatilla State Or.

CORNER DIAGRAM



T58 R33E

1/4

S30|S29

DESCRIBE CORNER MONUMENT FOUND

2 1/2" iron pipe with 3 1/4" brass cap (BLM) mkd.;

T58 R33E

1/4
S30|S29
1977

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

D. Fir, 13", N51°W, 12.5'; scribing visible..
W. Larch, 37", N70°E, 9.2'; " "
Tree is dying..

PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At. _____

Object Ident. _____

Ident. By _____

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner falls on Nly slope approx. 30' south of draw..

Signature

F.L. Munn

Title
PLS

Division

Headquarters

Date

10/26/91

7100-52-(3/68)

CORNER RECORD (PERPETUATION)

MONUMENT : DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

None.

ACCESSORIES : DESCRIBE NEW BT'S, WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

D. Fir, 12", N21°E, 10.5'; mkd.: $\frac{1}{4}$ S29 BT
 P. Pine, 12", S72 $\frac{1}{2}$ °E, 9.3'; mkd.: $\frac{1}{4}$ S29 BT
 P. Pine, 8", S21 $\frac{1}{2}$ °E, 55.8'; mkd.: $\frac{1}{4}$ S29 BT
 BTs have red blaze and band, BT tags and 54-9 signs. New BTs have alum. "PLS 1832" washers. 6' fence post with 54-9 sign within 5' of cor.

Work Done By F.S. Munro Title PLS 6/9/91 State Registration No. 1832
Date or Agency

Certified Cor. Record Prepared ? Yes No Filed At: Umatilla Co. Surveyor Date

REMARKS

Index File No. T-5 T. 58 R. 33E M. W.M. Tract or Surv. No. Cor.