

USDA-FOREST SERVICE

Index

File No.

W-5

CORNER RECORD (SEARCH)

N. Fk. (Ref. FSM 7151.4)

Tract or
Survey No.

Cor.
No.

T 58 R. 33E

R.D. John Day

County Umatilla

Merid. W.M.

N.F. Umatilla

State Or.

CORNER DIAGRAM



T58 R33E
S30/S29
S31/S32

1 DESCRIBE CORNER MONUMENT FOUND

2 1/8" iron pipe with 3 1/4" brass cap (BLM) mkd.:

T58 R33E
S30/S29
S31/S32
1977

2 DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

W. Larch, 26", N64°E, 13.4'; healed blaze.
W. Fir, 16", dead, N100W, 32.3'; scribing visible.
W. Fir, 11", dead, S49°E, 33.0'; " "
W. Fir, 27", dead, S50°W, 52.1'; " "

6 PHOTO IDENTIFICATION DATA

Photo No. _____
Filed At. _____
Object Ident. _____
Ident. By _____
Signature

7 PLANE COORDINATE POSITION DATA

State _____ Zone _____
X _____
Y _____
Estab. By _____
Agency

3 DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Cor. falls on NE edge of Cr. Posted line N and S.

Signature

FL Munro

Title
PLS

Division

Headquarters

Date

10/26/91

7100-52-(3/68)

CORNER RECORD (PERPETUATION)

MONUMENT : DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

None.

ACCESSORIES : DESCRIBE NEW BT'S, WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

W. Fir, 20", N28°W, 93.4'; mkd.: T5S R33E S30 BT
Spruce, 14", S45¹/₈°E, 40.3'; mkd.: T5S R33E S32 BT
5/8"x 30" rebar, 26" in ground, S39°W, 25.7'; yellow plastic cap
mkd.: PLS 1832

BTs have red blaze and band, BT tags and 54-9 signs. New BTs have
alum. "PLS 1832" washers. 6' fence post with 54-9 sign within
5' of cor..

Work Done By F.S. Munro Title PLS Date 10/26/91 State Registration No. 1832
or Agency

Certified Cor. Record Prepared ? Yes No Filed At: Umatilla Co. Surveyor Date

REMARKS

Index File No. V-5 T. 5S R. 33E M. W.M. Tract or Surv. No. Cor.