

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

X-5


History of original corner establishment:

George S. Pershin under G.L.O. Contract No. 430, dated Mar. 23, 1882, set a basalt stone 14"x 10"x 6", 10" in ground. Stone marked 1/4 on N. face. From the corner:

Pine, 20" dia., N48°E, 28 lks.
Pine, 42" dia., N46°W, 92 lks.

Craig L. Wanless, Cadastral Surveyor, under special instructions, Group No. 350, found a basalt stone 14"x 10"x 6" marked 1/4. He set a 2 1/2"x 28" iron post with brass cap marked:

From the corner:
A Pine, 29" dia., N66°E, 28 lks.; scribing visible. (orig.)
Pine stump, 26" dia., N46°W, 92 lks.; scribing visible. (orig.)
Lodgepole Pine, 12" dia., N10°W, 149 lks. (new BT)



T5S R33E
1/4
S31 | S32
1977

Description of corner evidence found:

I found a 2 1/2" iron pipe with a 3 1/4" brass cap (BLM) marked as above. Monument is in mound of stone. From the corner:
Ponderosa Pine, 13" dia., N10°W, 104.4 ft.; scribing visible.
Ponderosa Pine, 29" dia., N66°E, 18.5 ft.; " "
Ponderosa Pine stump, approx. 34" dia., N46°W, 60.7 ft.; fragmentary scribing on weathered blaze.

Description of monument and accessories I established to perpetuate the original location of this corner:

I marked new BTs:
Ponderosa Pine, 18" dia., S85°E, 50.1 ft.; marked: 1/4 S32 BT
Ponderosa Pine, 13" dia., S64°E, 104.5 ft.; marked: 1/4 S32 BT
BTs have blaze and a 6" band painted red, BT tags and "Land Survey Monument" signs. New BTs have, additionally, alum. "PLS 1832" washers nailed to the bottom of the blaze. There is a 6' steel fence post with a "Land Survey Monument" sign within 5' of the corner.
Measured to center of BTs using steel tape and staff compass. Magnetic declination set at 19°E.

June 9, 1991

REGISTERED PROFESSIONAL LAND SURVEYOR

Fayette S. Munro

OREGON JULY 13, 1979 FAYETTE S. MUNRO 1832

Office of..... County of.....
State of..... I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Surveyor

Date 12-9-91

Rec'd By XR

No. 91-97-R