


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

George S. Pershin under G.L.O. Contract No. 362, dated Aug. 2, 1880, set a basalt stone 24"x 14"x 8". From corner:
Pine, 40" dia., N67°W, 39 lks.
Pine, 6" dia., N46°E, 19 lks.



Continued on Page 2 of 2.

Description of corner evidence found:

I found a 2½" iron pipe with a 2½" brass cap marked: Monument was in mound of stone. From the corner: T5S R33E S31|S32 S5 T6S 1984 PLS 933

A Ponderosa Pine stump, badly decayed, size indeterminate, N67°W, 25.7 ft. to blaze; scribing visible on burned and decayed blaze.

A Lodgepole Pine, 9" dia., N51°W, 81.6 ft.; with scribing visible.

A Ponderosa Pine, 28" dia., N21°E, 61.8 ft.; with scribing visible.

Description of monument and accessories I established to perpetuate the original location of this corner:

I marked new BTs:
A Douglas Fir, 11" dia., N47 3/4°E, 39.7 ft.; marked: T5S R33E S32 SC BT
5/8"x 30" iron pin (rebar) driven 25" in ground, N63¼°E, 14.6 ft.; with 1½" yellow plastic cap marked: PLS 1832

BTs have blaze and a 6" band painted red, BT tags and "Land Survey Monument" signs. New BT has, additionally, an alum. "PLS 1832" washer nailed to the bottom of the blaze. There is a 6' steel fence post with a "Land Survey Monument" sign within 5' of the corner.

Measured to center of BTs using steel tape and staff compass. Magnetic declination set at 18°E.

June 14, 1991

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Fayette S. Munro

OREGON
JULY 13, 1979
FAYETTE S. MUNRO
1832

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19....
..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)


RECEIVED BY
Umatilla County Surveyor
Date 12-91
Rec'd by KK
No. 91-97-R

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Z-5

History of original corner establishment:

David H. Krumbeln, PLS 933, set a 2 $\frac{1}{2}$ " galvanized pipe with a 2 $\frac{1}{2}$ " brass cap at record bearing and distance from single remaining BT. Cap marked:
From corner:
Ponderosa Pine stump, 40" dia., N67°W, 39 lks.; scribing visible. (orig. BT)
Ponderosa Pine, 24" dia., N21°E, 65.5 ft.
Lodgepole Pine, 8" dia., N51°W, 81.6 ft.



T5S R33E
S C
S31 | S32
S5
T6S
1984
PLS 933

Description of corner evidence found:

Description of monument and accessories I established to perpetuate the original location of this corner:

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Fayette S. Munro

OREGON
JULY 13, 1979
FAYETTE S. MUNRO
1832

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor
Date 12-96
Rec'd By KK
No. 91-97-R