


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. D-18

History of original corner establishment:

There was no corner originally set




Description of corner evidence found:

Description of monument and accessories I established to perpetuate the original location of this corner:

At surveyed point set 2 1/2" X 30" galvanized pipe with brass cap stamped:

set pipe 22" in ground with mound of stone to cap.



Bearing Trees:

A Tamarack 7" dia. bears N88°E, 19.7 ft., scribed SW 1/16 S2 BT.
A Douglas Fir 10" dia. bears N 71°W, 30.0 Ft., scribed SW 1/16 S2 BT.

Attached 54-3 & 54-4 signs to both BTs. Attached brass washer stamped LS1294 to new BTs. Painted blazes and 6" band around both BTs red. Attached 54-2 & 54-4 signs to metal post 6' west of corner. Attached 54-2 & 54-9 signs to metal fence post 6' north of corner.



I hereby certify the above corner monument was re-established as herein described on June 27, 1980.

Witnesses: R. Orton
G. Orton
D. Allen

Office of..... County Surveyor..... County of..... Umatilla
Oregon....., I hereby certify that the within instrument was filed in this office
for record on the..... day of..... December..... 19..... 80
..... by.....
(COUNTY OFFICIAL) (DEPUTY)