


History of original corner establishment:

Unsurveyed - subdivided section.



No record of subsequent remonumentation found in County Records.

Description of corner evidence found:


None.

Description of monument and accessories established to perpetuate the original location of this corner

Set 2½" x 30" iron pipe 2" in ground with brass cap marked as shown: from which I scribed Bearing Trees:

- A pine 9" diameter bears North 21°55' West 63.50 feet marked E 1/16 S 1 BT
- A fir 7" diameter bears South 04°56' East 13.60 feet marked E 1/16 S 12 BT

I nailed a brass washer marked PLS 933 to the BT blaze of both trees. Set a steel fence post 5 feet West of corner. The corner is South 26 feet from an East-West fence line. Used T-2 and steel tape, measuring a horizontal distance to the center of the Bearing Trees.



Office of _____ County Surveyor _____ County of _____ Umatilla _____
 State of _____ Oregon _____, I hereby certify that the within instrument was filed in this office
 for record on the _____ day of _____
 _____ by _____
 (COUNTY OFFICIAL) (DEPUTY)