

Index
 File No. E 11
 T 5 S R. 34 E
 Merid. Willamette


CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or
 Survey No. _____ Cor. S. 1/4 Cor.
 No. Sec. 9

R.D. La Grande County Union
 N.F. Wallowa-Whitman State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

found stone

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

In section 4 found pine 28" in diam with blaze and in good shape.
 In section 9, found down tamarack log with scribe.
 The Pine BT bears N53°E, 32 Lks distance marked 1/4 S B.T.

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Take Fire Trough Road S442

PHOTO IDENTIFICATION DATA

Photo No. _____
 Filed At. _____
 Object Ident. _____
 Ident. By _____
Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____
 X _____
 Y _____
 Estab. By _____
Agency

Signature
 J. G. Voelz

Title
 Co. Surveyor

Division

Headquarters
 La Grande


Date
 Sept. 1970

7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 30" galvanized pipe with bronze cap on top.
The hole was backfilled with stone and tamped soil.
I stamped the disk.



ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

Red fir 8" in diam bears S32°W at a distance of 2.9 ft. scribe 1/2 SBT.
Placed bearing tree signs on both old and new bearing trees and painted stripe around the trees. Placed a steel fence post with USFS sign 54-4 attached near the corner.

Work Done By. J. G. Voelz Title Co. Surveyor Date 1970 State Registration No. Ore Lic 381
or Agency

Certified Cor. Record Prepared ? Yes No Filed At: La Grande, Oregon Date Sept. 1970

REMARKS