


History of original corner establishment:

T. 5 S., R. 33½ E., Willamette Meridian, Oregon



The following field notes describe the remonumentation of certain original corner points, township 5 south, range 33½ east, Willamette Meridian, Oregon, as provided for in the General Special Instructions, Group Number 350, Oregon, dated May 3, 1957, "Investigation of Collateral or Physical Evidence of Corner Positions and Accessories Followed by Remonumentation of Corner Points, with New Accessories when Needed".

The remonumentation of original corner points was made at the request of the United States Forest Service, in conjunction with their Land Line Location Program.

The mean magnetic declination is 20° E.

The ¼ sec. cor. of secs. 7 and 12, on the E. bdy. of the Tp., monumented with the original basalt stone, 20 x 10 x 10 ins., loosely set 1 in. in the ground, mkd. ¼ on W. face, from which the remains of the original bearing trees:

A fir, 30 ins. diam., bears N. 80° W., 106 lks. dist., with fragmentary scribe marks visible on open blaze.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 22 ins. in the ground, with brass cap mkd.

T 5 S    3-1  
¼  
R 33½ E | R 34 E  
S 12 | S 7    G-1  
1977

from which a new bearing tree

A pine, 17 ins. diam., bears S. 39° E., 31 lks. dist., mkd. ¼ S7 BT.

Deposit corner stone alongside iron post.

This Certified Record Was Made From BLM Field Notes of The Remonumentation of Original Corners Under Special Instructions Dated May 3, 1957. Survey Completed October 4, 1977

Office of..... County of.....  
State of..... I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19..... EARL E STRANG  
..... by..... L/1993  
(COUNTY OFFICIAL) (DEPUTY)