


J-11

History of original corner establishment:

Corner was established in 1882, by Rufus S. Moore, under General Land Office Contract No. 451. Surveyor General's records state: Set a post 3 ft. long, 3 in. square and 2 1/4 in. in the ground for 1/4 corner, marked 1/4 S on the W. face, from which: A pine 8" dia. bears S 60 W, 56 lks. dist. marked 1/4 S BT. A pine 2 1/4" dia. bears N 08 E, 10 lks. dist. marked 1/4 S BT.



Description of corner evidence found:

At assumed corner location I found no trace of the wood post as previously described. However I did find a 2 1/4" pine stump with traces of a blaze, though the tree was cut below the scribing. This tree was in Section 9. There was no trace of the 8" tree as described and being in Section 16.

Description of monument and accessories established to perpetuate the original location of this corner:

As the evidence in the vicinity of the corner agrees with the GLO original record, at the location reconstructed from the position of the original bearing tree, I set a 2 1/2" brass cap on a 30" galv. iron pipe, and being stamped as shown above, with a large mound of stone and dirt around, and of which buried the monument.

New bearing trees:

A pine 7" in dia. bears N 55 E, 21.0 feet and scribed 1/4 S S 9 Bt.
A pine 8" dia. bears S 38 E, 55.0 feet and scribed 1/4 S S 16 BT.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

James H. Hambleton
8-21-78

OREGON
JULY 10, 1964
JAMES H. HAMBLETON
645

I hereby certify the above corner monument was re-established as herein described in August 1978.

Witnesses: *Leonard E. Brown*
Crew Chief
J. W. Smith
Instrument Man

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

J-11

93-39-B