


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

1-9

History of original corner establishment:

Original survey by General Land Office contract survey
The original notes read;
Set a post from which; A pine 5" in diam bears N50°E 123 lks
marked T5S R34E S9BT;
A pine 6" in diam bears N12°W 354 lks dist marked T5S R34E S8BT.
A pine 4" in diam bears S87°E 156 lks marked T5S R34D S16BT
No other trees with in limits.




Description of corner evidence found:

Found a 8" snag with scribe at S87°E 156 lks dist.

Description of monument and accessories established to perpetuate the original location of this corner

At the position of the corner I set a 2" galvanized pipe 30" long with bronze cap on top and 8" plate welded to bottom. The pipe set to a depth of 24" and backfilled with stone and soil.

I stamped the disk



From the monument the original bearing trees are none.
I set the following new bearing trees;
A pine (black) 8" in diam bears N49E 152.5 ft. marked
T5S R34E S9 BT; A pine (black) 12" in diam bears S84°E 97.2 ft.
marked T5S R34E S16BT. ; A black pine 26" in diam bears S55°W
541 ft. marked T5S R34E S17BT; A black pine 7" in diam bears N10°W
237.4 ft. marked T5S R34E S8BT; (trees measured to respective centers and
marked with scribe) I set a steel fence post with USFS sign 54-4 attached.
Bearing tree sign were placed on bearing trees shoulder high facing the monument.

Office of.....County.....surveyor..... County of..... Union.....
State of.....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the ...10... day of ...Sept....., 1969, at ...9... o'clock ...A... m., (signed)
..... County surveyor by
(COUNTY OFFICIAL)

93-39-B