

Index
File No. K-8

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or
Survey No. _____

Cor.
No. _____

T 5 S R. 34 E

R.D. La Grande County Union

Merid. Willamette

N. F. Wallow-Whitman State Oregon

CORNER DIAGRAM

T 5 S R 34 E
NE 1/16 S 17



1993

PLS 1106

DESCRIBE CORNER MONUMENT FOUND

None. Corner established as part of this survey.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None.

PHOTO IDENTIFICATION DATA

Photo No. _____
Filed At. _____
Object Ident. _____
Ident. By _____

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____
X _____
Y _____
Estab. By _____

Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner is on very slight South slope in a young lodgepole pine thicket, approx. 1500' East of Road No. 5160-344 (road closed).

Signature
Will R. Wells

Title
Land Surveyor

Division
Headquarters
Pendleton, OR, 10-28-93

Date
FS-7100-52 (3/68)

6

7

8

2

3

4

5

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

At position established by survey...

Set a 2 1/2" aluminum cap on 2 1/2"x30" aluminum pipe 25" in ground surrounded with large stone mound.

Set steel fence post 3.5' North of corner & attached sign 54-9 & 54-2.

Compass declination 18° East.

9

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

New bearing trees established:

A 13 1/2" diam. Western larch brs. N04° E, 58.4' scribed NEL/16S17 BT.

A 13 1/2" diam. Western larch brs. N78° W, 46.1' scribed NEL/16S17 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 & 54-9, painted face of blaze & a 6" red band around each BT.

10

Work Done By W.R.Wells Title Land Surveyor Date 10-28-93 State Registration No. PLS 1106 or Agency

Certified Cor. Record Prepared ? Yes ~~XXX~~ Filed At Unatilla County Surveyor Date 8/94

11

REMARKS

12

13