


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

L-5

History of original corner establishment. Corner was originally established by Rufus S. Moore, U.S. Deputy Surveyor, under Contract No. 451, dated June 12, 1882. Surveyor General records state: Set a post 3 ft. long 3 ins. sq. 24 ins. in ground for 1/4 sec. cor. marked 1/4 S on W. face. from which: A pine 8 ins. in dia. bears S 73° E 10 lks dist. marked 1/4 S BT. A pine 8 ins. in dia. bears S 63° W 15 lks dist. marked 1/4 S BT.



Description of corner evidence found:

None. Corner re-established by single proportionate measurement between the recovered Southwest corner of Section 17 and the monumented Northwest corner of Section 17.

This corner was searched by a 2 person crew for a total of 4 hours on 2 separate occasions. 1 1/2 hours of professional land surveyor time was spent searching. A search radius of 150 feet was covered. The corner area has been logged and burnt years ago.

Description of monument and accessories established to perpetuate the original location of this corner:

At position determined by survey...

Set a 2 1/2" X 30" aluminum pipe with 2 1/2" aluminum cap, 24" in ground and surrounded with a mound of earth and stone to cap, marked as shown in corner diagram.

Attached sign 54-9 to steel fence post, set 4.0 feet North of monument.

New bearing trees established:

- A 8 1/2" western larch bears N 03° W - 111.0 feet, scribed: 1/4S18 BT.
A 9" western larch bears N 27 1/2° E - 57.6 feet, scribed: 1/4S17 BT.
A 9" western larch bears S 45° E - 48.4 feet, scribed: 1/4S17 BT.
A 18" douglas fir bears S 05° W - 72.6 feet, scribed: 1/4S18 BT.

New bearing trees have a brass washer stamped 'PLS 1106' nailed to face of blaze. Attached sign 54-3 & 54-9, painted face of blaze & a 6" red band around each bearing tree.

I hereby certify that the above corner was properly re-established to U.S.F.S standards by me on October 26, 1993.

Compass declination 18° East.

REGISTERED PROFESSIONAL LAND SURVEYOR

William R. Wells

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

renews 12-31-94

Office of... County of... State of... I hereby certify that the within instrument was filed in this office for record on the... day of... 19... by... (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY Umatilla County Surveyor Date 8-4-94 Rec'd By KK No. 94-106-B 9

*GPO-591-971, 1988