


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

N-1

History of original corner establishment:

Corner was originally established by Rufus S. Moore, U.S. Deputy Surveyor, under Contract No. 451, dated June 12, 1882. Surveyor General records state: Set a post 4 ft long 4 ins square 24 ins in the ground for the cor to Secs. 13, 18, 19 & 24 marked T5S. S 18 on NE R34E S 19 on SE R33½E S24 on SW and S 13 on NW faces with 3 notches on the N&S edges. from which:



A tamarack 20 ins diam. bears N 8 E 50 lks. dist.

marked: T5S,R34E S18 B.T.

A tamarack 13 ins diam. bears S 5° E 125 lks. dist.

marked: T5S,R34E S19 B.T.

A pine 12 ins. diam. bears S 57° W 120 lks. dist. marked T5S, R33½E S24 B.T.

A fir 8 ins. diam. bears N 66° W 35 lks. dist. marked T5S, R33½E S13 B.T.

Description of corner evidence found:

A 23" western larch bears N8°E-33.0 feet, with open blaze and visible scribing.

A 22" western larch bears S5°E-82.5 feet, with open blaze and visible scribing.

Re-established corner position by distance-distance intersection from the two existing bearing trees.

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2½"x30" aluminum pipe with 2½" aluminum cap, 24" in ground and surrounded with a mound of earth to cap, marked as shown in corner diagram.

Attached sign 54-9 to steel fence post, set 4.0 feet West of monument.

New bearing trees established:

A 9" lodgepole pine bears S 41° E - 25.6 feet, scribed T5SR34ES19 BT.

A 9" white fir bears S 42° W - 142.6 feet, scribed: T5SR33½ES24 BT.

A 8" alpine fir bears N 64° W - 45.5 feet, scribed: T5SR33½ES13 BT.

New bearing trees have a brass washer stamped 'PLS 1106' nailed to face of blaze. Attached sign 54-3 & 54-9, painted face of blaze & a 6" red band around each bearing tree.

I hereby certify that the above corner was properly re-monumented to U.S.F.S standards by me on October 18, 1993.

Compass declination 18° East.

REGISTERED PROFESSIONAL LAND SURVEYOR

William R. Wells

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

renews 12-31-94

Office of County Surveyor..... County of Umatilla

State of Oregon....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by

(COUNTY OFFICIAL)

(DEPUTY)

RECEIVED BY

Form R6-7100-57 (9/71)

Umatilla County Surveyor

Date 8-4-94

Rec'd By SK

No. 94-106-C

11