


11-13

History of original corner establishment:

Corner was established in 1882, by Rufus S. Moore, under General Land Office Contract No. 451. Surveyor General's records state: Set a post 4 ft. long 4" square, 24" in ground for corner to Sec's. 15, 16, 21 & 22 marked T 5 S S 15 on NE, R 34 E S 16 on NW, S 21 on SW and S 22 on the SE faces with 3 notches on the S and E edges from which:  
 A pine 8" dia. bears S 17 W 54 lks. dist. marked T 5 S R 34 E S 21 BT.  
 A fir 5" dia. bears S 32 W 15 lks. dist. marked T 5 S R 34 E S 22 BT.  
 A tamarack 6" dia. bears N 23 W 43 lks. dist. marked T 5 S R 34 E S 16 BT.  
 A pine 5" dia. bears N 47 E 49 lks. dist. marked T 5 S R 34 E S 15 BT.



Description of corner evidence found:

At assumed corner location I found no trace of the original section corner, nor any evidence of the bearing trees, as there was evidence of a fire in the early 1900's through this area of which destroyed all evidence of the original corner.

Description of monument and accessories I established to perpetuate the original location of this corner:

Assuming this corner to be lost, I then used double proportioning measurements to re-establish the section corner, thus I set a 2 1/2" brass cap on a 30" galv. iron pipe, and being stamped as shown above, with a large mound of stone and dirt around, and of which buried the monument.

New bearing trees:

A tamarack 9" dia. bears N 70 E, 21.42 feet scribed T 5 S R 34 E S 15 BT.  
 A tamarack 11" dia. bears N 38 W, 33.67 feet scribed T 5 S R 34 E S 16 BT.  
 A tamarack 8" dia. bears S 22 W, 35.9 feet scribed T 5 S R 34 E S 21 BT.  
 A tamarack 12" dia. bears S 10 E, 27.67 feet scribed T 5 S R 34 E S 22 BT.

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

*James H. Hambleton*  
 8-21-78

OREGON  
 JAMES H. HAMBLETON  
 625

I hereby certify the above corner monument was re-established as herein described in August 1978.

Witnesses: *Leonard C. Green*  
 Crew Chief  
*J. D. Hinkle*  
 Instrument/Man

N-13

Office of..... County of.....  
 State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....  
 ..... by .....  
 (COUNTY OFFICIAL) (DEPUTY)

93-39-B