

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

R-5

History of original corner establishment:


Corner was originally established by Rufus S. Moore, U.S. Deputy Surveyor, under Contract No. 451, dated June 12, 1882. Surveyor General records state: Set a post 4 ft long 4 ins square 24 ins in the ground for the sec. corn. to sections 19, 20, 29, and 30, from which:

A pine 4 ins. diam. bears S 46° W 11 lks. dist. marked: T5S R34E S30 BT.

A pine 4 ins. diam. bears N 40° W 28 lks. dist. marked: T5S R34E S19 BT.

A pine 5 ins. diam. bears N 30° E 7 lks. dist. marked: T5S R34E S20 BT.

A pine 4 ins. diam. bears S 53° E 25 lks. dist. marked: T5S R34E S29 BT.



Description of corner evidence found:

Nothing found of original evidence. This corner was not re-established on this survey.

Corner area was searched on 2 separate occasions with a 2 person crew. Total search time was 4 hours. 2 hours of professional land surveyor time was spent searching. A 150 foot radius search area was covered.

The corner area is in a mature lodgepole pine stand, with most trees dead and down. The trees are approximately 60-90 years old.

Corner search area was determined by closed traverse control survey.

Description of monument and accessories established to perpetuate the original location of this corner:

August 4, 1994
 REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

Will: R. Wells
 OREGON
 JULY 22, 1977
 WILLIAM R. WELLS
 1106

renews 12-31-94

Office of County Surveyor County of Umatilla
 State of Oregon, I hereby certify that the within instrument was filed in this office
 for record on the day of , 19
 _____ by _____
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
 Umatilla County Surveyor
 Date 8-4-94
 Rec'd By KK
 No. 94-106-C

*GPO-591-971, 1988