



7-31-01

**LAND CORNER RECORD**

**GRANTOR/SURVEYOR/PUBLIC OFFICER:** This corner record correctly represents work performed by me or under my direction in conformance with the Survey Recording Act.

**COMPANY OR AGENCY:** William R. Wells Land Surveying

**ADDRESS:** P.O. Box 1696  
357 NE Hwy. 11  
Pendleton, OR 97801

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-02  
7/31/01*

**GRANTEE: PUBLIC**

SEAL/SIGNATURE/DATE

**LEGAL:** TWP: 6N RGE: 32E CORNER CODE: A-1

**ADDITIONAL IDENTIFIER:** (BLM designation, street or plat names, block, lot, etc.)  
NORTHWEST CORNER OF SECTION 6.

**COUNTY:** Walla Walla

**OREGON PLANE COORDINATES:** N: 868431.69 E: 8616507.36, (inf ORN 83/91)

**ORDER:**

**CORNER INFORMATION:** Discuss the history, evidence found, and perpetuation of the corner. Diagram the references; provide the date of work; and, if applicable, a reference to a map of record and/or the field book/page no. Use the back, if needed.

**1. HISTORY:**

A. Most recent approved record is resurvey by Edwin Richard, under Special Instructions dated February 22, 1867. Record states: Intersect mound with trench and pits but without post, in which I set a new post for corner to Townships 6 & 7 North, Ranges 31 & 32 East. Continued on back.....

**2. EVIDENCE FOUND:**

Fence corner with fences extending North-South and West.

**3. PERPETUATION INFORMATION:**

At the East side of said fence corner set a 2 1/4" brass cap on a 1" x 30" galvanized iron pipe 6" below ground level. Cap is marked:

T 7 N  
R31E R32E  
S36 | S31  
S1 | S6  
T 6 N  
2001  
OPLS 1106  
WPLS 17372

From which:

A brass washer stamped "PLS 1106", 4" above ground level in North side of fence post bears S 01° E, 53.7 feet.  
A brass washer stamped "PLS 1106", 4" above ground level on West side of South end of H brace bears N 01° W, 16.2 feet. Set steel fence post 1.0 Feet South of brass cap. Compass declination 18° East.

This form is in compliance with the intent of RCW 65.04.045 and prescribed by the Public Land Survey Office, Department of Natural Resources - 1/97.

6N32A1ORN

RECEIVED BY  
Umatilla County Surveyor  
Date 9-01  
Rec'd By [Signature]  
No. 01-111-B