



7-31-01

LAND CORNER RECORD

GRANTOR/SURVEYOR/PUBLIC OFFICER: This corner record correctly represents work performed by me or under my direction in conformance with the Survey Recording Act.

COMPANY OR AGENCY: William R. Wells Land Surveying

ADDRESS: P.O. Box 1696
357 NE Hwy. 11
Pendleton, OR 97801

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

*renews 6-30-02
7/31/01*

GRANTEE: PUBLIC

SEAL/SIGNATURE/DATE

LEGAL: TWP: 6N RGE: 32E CORNER CODE: A-17

ADDITIONAL IDENTIFIER: (BLM designation, street or plat names, block, lot, etc.)
NORTHWEST CORNER OF SECTION 2

COUNTY: Walla Walla

OREGON PLANE COORDINATES: N: 868612.23 E: 8637705.83, (inf ORN 83/91)

ORDER:

CORNER INFORMATION: Discuss the history, evidence found, and perpetuation of the corner. Diagram the references; provide the date of work; and, if applicable, a reference to a map of record and/or the field book/page no. Use the back, if needed.

1. HISTORY:

Corner originally established by Daniel G. Major under contract No. 72, dated May 25, 1863. Record states: Set a post for corner to Sections 34 & 35, made mound with trench and pits and drove charred stake.

Corner shows as a "stone" on 1900 survey plat recorded as File # 2-U-97, Walla Walla County Engineer's Office.

2. EVIDENCE FOUND:

Found 11" X 10" set stone 8" above ground. No visible marks, only rock in the area. Stone is firmly set upright in ground with top broken, probably by farm implement.

3. PERPETUATION INFORMATION:

Chiseled an "X" on North face of stone for measure point. Set steel fence post 1' South of stone.
Brass cap on iron pipe monumenting the North 1/4 Corner of Section 3 bears N 89° 15' 17" W., 2644.74'.
Bearings are based on true north, see accompanying Record of Survey.

This form is in compliance with the intent of RCW 65.04.045 and prescribed by the Public Land Survey Office,
Department of Natural Resources - 1/97.
16N32A17ORN

RECEIVED BY

Umatilla County Surveyor

Date 9-01

Rec'd By [Signature]

No. 01-111-B