



7-31-01

**LAND CORNER RECORD**

**GRANTOR/SURVEYOR/PUBLIC OFFICER:** This corner record correctly represents work performed by me or under my direction in conformance with the Survey Recording Act.

**COMPANY OR AGENCY:** William R. Wells Land Surveying

**ADDRESS:** P.O. Box 1696  
357 NE Hwy. 11  
Pendleton, OR 97801

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Will. R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-02  
7/31/01*

**GRANTEE: PUBLIC**

SEAL/SIGNATURE/DATE

**LEGAL:** TWP: 6N RGE: 32E CORNER CODE: E-13

**ADDITIONAL IDENTIFIER:** (BLM designation, street or plat names, block, lot, etc.)  
NORTHWEST CORNER OF SECTION 10.

**COUNTY:** Walla Walla

**OREGON PLANE COORDINATES:** N: 863156.45 E: 8632511.02, (inf ORN 83/91)

**ORDER:**

**CORNER INFORMATION:** Discuss the history, evidence found, and perpetuation of the corner. Diagram the references; provide the date of work; and, if applicable, a reference to a map of record and/or the field book/page no. Use the back, if needed.

**1. HISTORY:**

Corner originally established by Daniel G. Major under Contract No. 72, dated May 5, 1863. Record states: Set post for corner to Sections 3, 4, 9 10 on slope of stony mountain, well up and at head of small ravine. Built mound dug trench & pits sodded.

**2. EVIDENCE FOUND:** Held the mean intersection of old rock piles extending N-S and E-W. These old rock piles used to support fence jacks or fence posts, wire and posts now removed. Old cattle path next to removed fence is visible to the South.

**3. PERPETUATION INFORMATION:** At mean intersection described above, set a 2 1/2" aluminum cap on a 2 1/2" x 30" aluminum pipe, with the top of cap 4" above ground level. Monument marked as shown:

T6N R32E  
S4 | S3  
S9 | S10  
2001  
PLS 17372

Corner is located about 2 feet South of the South edge of 8' dirt road leading to Vansycle Canyon. Set steel fence post North of corner monument.

This form is in compliance with the intent of RCW 65.04.045 and prescribed by the Public Land Survey Office, Department of Natural Resources - 1/97.

\6N32E13ORN

RECEIVED BY  
Umatilla County Surveyor  
Date 7-01  
Rec'd By KP  
No. 01-111-B