



7-31-01

**LAND CORNER RECORD**

**GRANTOR/SURVEYOR/PUBLIC OFFICER:** This corner record correctly represents work performed by me or under my direction in conformance with the Survey Recording Act.

**COMPANY OR AGENCY:** William R. Wells Land Surveying

**ADDRESS:** P.O. Box 1696  
357 NE Hwy. 11  
Pendleton, OR 97801

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Will. R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

renews 6-30-02  
7/31/01

**GRANTEE: PUBLIC**

SEAL/SIGNATURE/DATE

**LEGAL:** TWP: 6N RGE: 32E **CORNER CODE: J-17**

**ADDITIONAL IDENTIFIER:** (BLM designation, street or plat names, block, lot, etc.)

NORTHWEST CORNER OF SECTION 14.

**COUNTY:** Walla Walla

**OREGON PLANE COORDINATES:** N: 857979.34 E: 8638077.06, (inf ORN 83/91)

**ORDER:**

**CORNER INFORMATION:** Discuss the history, evidence found, and perpetuation of the corner. Diagram the references; provide the date of work; and, if applicable, a reference to a map of record and/or the field book/page no. Use the back, if needed.

**1. HISTORY:**

Corner originally established by Daniel G. Major under Contract No. 72, dated May 5, 1863. Record states: Set section post for corner to Sections 10, 11, 14, 15 on side of high mountain ridge, bearing NW. Bearing to rock on W side of ridge N 30°38' E dist. 3/4 m. To the most Westerly of a number of prominent rocks, on top of ridge N 12°05' W dist. 3 1/2 miles.

**2. EVIDENCE FOUND:** Found small circle of stones, 3 feet in diameter, on flat spot in extremely steep East slope of ridge—stones all evenly spaced and arranged in a circle— a cute little monument! This area has not been disturbed, hardly even by cattle, because it is so steep. Major's record accessory bearings fit reasonably well, when measured with a hand compass.

**3. PERPETUATION INFORMATION:**

At center of the circle of stones, set a 2 1/2" aluminum cap on a 2 1/2" x 30" aluminum pipe, Cap of monument is, 4" above ground level, marked as shown below:

T6N R32E  
S10 | S11  
S15 | S14  
2001  
PLS 17372

From which:

A 5/8" x 30" iron rebar with yellow plastic cap stamped "OR PLS 1106 WA PLS 17372", bears S 38° E, 41.5 feet.

A 5/8" x 30" iron rebar with yellow plastic cap stamped "OR PLS 1106 WA PLS 17372", bears N 38 1/2° W, 41.7 feet.

Set a steel fence post near new corner monument. Compass declination 18° East.

This form is in compliance with the intent of RCW 65.04.045 and prescribed by the Public Land Survey Office, Department of Natural Resources - 1/97.

16N32J17ORN

RECEIVED BY

Umatilla County Surveyor

Date 09-01

Rec'd By KP

No. 01-111-B