



LAND CORNER RECORD

GRANTOR/SURVEYOR/PUBLIC OFFICER: This corner record correctly represents work performed by me or under my direction in conformance with the Survey Recording Act.

COMPANY OR AGENCY: William R. Wells Land Surveying

ADDRESS: P.O. Box 1696
357 NE Hwy. 11
Pendleton, OR 97801

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will. R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

*renews 6-30-02
7/30/01*

GRANTEE: PUBLIC

SEAL/SIGNATURE/DATE

LEGAL: TWP: 6N RGE: 32E CORNER CODE: J-5

ADDITIONAL IDENTIFIER: (BLM designation, street or plat names, block, lot, etc.)

NORTHWEST CORNER OF SECTION 17.

COUNTY: Walla Walla

OREGON PLANE COORDINATES: N: 857764.42 E: 8622330.08, (inf ORN 83/91)

ORDER:

CORNER INFORMATION: Discuss the history, evidence found, and perpetuation of the corner. Diagram the references; provide the date of work; and, if applicable, a reference to a map of record and/or the field book/page no. Use the back, if needed.

1. HISTORY:

Corner originally established by Daniel G. Major under Contract No. 72, dated May 5, 1863.
Record states: Set post for corner to Sections 7, 8, 17, 18 on side of high hill. Built mound deposited charred stake, dug trench & pits. Bearing to Tree on Walla Walla N 58°23'E, dist 4 3/4 miles Rock abutting from high ridge S 84°07' W dist 2 1/2 miles.

Corner is shown as "Old Gov't Cor-Rock" on survey plat by L. W. Lochr for George Lambdin, File # 2-S-047, Walla Walla County Engineer's Office.

2. EVIDENCE FOUND:

At fence corner with fences extending East and South, found and uprooted 16 x 12 x 6" basalt stone, marked "X".

3. PERPETUATION INFORMATION:

At a point on the SE side of the fence corner, set a 2 1/4" brass cap on a 1" x 30" galvanized iron pipe 6 inches above ground. Placed marked stone alongside. Cap is marked:

T6N R32E
S7 | S8
S18 | S17
2001
OPLS 1106
WPLS 17372

From which:

The second steel fence post from fence corner in fence running East bears N 90° E, 65.0 feet.
The second steel fence post from fence corner in fence running South bears S 04° W, 61.6 feet.
Set steel fence post North of new monument. Measured bearings and distances to steel fence posts are at ground level. Compass declination 18° East.

This form is in compliance with the intent of RCW 65.04.045 and prescribed by the Public Land Survey Office, Department of Natural Resources - 1/97.
V6N32J5ORN

RECEIVED BY

Umatilla County Surveyor

Date 9-01

Rec'd By RR

No. 01-11-B