



7-31-01

LAND CORNER RECORD

GRANTOR/SURVEYOR/PUBLIC OFFICER: This corner record correctly represents work performed by me or under my direction in conformance with the Survey Recording Act.

COMPANY OR AGENCY: William R. Wells Land Surveying

ADDRESS: P.O. Box 1696
357 NE Hwy. 11
Pendleton, OR 97801

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-02

7/30/01

GRANTEE: PUBLIC

SEAL/SIGNATURE/DATE

LEGAL: TWP: 6N RGE: 32E

CORNER CODE:

7.5 MILE

ADDITIONAL IDENTIFIER: (BLM designation, street or plat names, block, lot, etc.)

STATE LINE 7 1/2 MILE CORNER

COUNTY: Walla Walla

OREGON PLANE COORDINATES: N: 855450.24 E: 8629647.27, (inf ORN 83/91)

ORDER:

CORNER INFORMATION: Discuss the history, evidence found, and perpetuation of the corner. Diagram the references; provide the date of work; and, if applicable, a reference to a map of record and/or the field book/page no. Use the back, if needed.

1. HISTORY:

Corner originally established by Daniel G. Major, under Contract No. 72, dated May 25, 1863. Record states: Made excavation, 2 ft. deep, planted an alder post, 5 ft. long & 6 ins. sq., top beveled; marked on W. face "1/2 M". Deposited a white thorn stake, 15 ins. long; moved 2 large stones to post. Erected mound, 6 ft. sq. at base and 3 ft. high, tapering to top of post; earth pack & sodded. Dug deep trench & pits, as usual. 40 lks. S. & S.E. from post, a ledge of rock "puts out".

2. EVIDENCE FOUND:

Found 2 large set stones and post remains below ground level. Ledge of exposed rock in wash bears S. S.E., 40 links.

3. PERPETUATION INFORMATION:

At location of found post remains between the two large stones, set a 2 1/4" brass cap on a 1" x 30" galvanized iron pipe with top of cap projecting 4" above ground. Cap marked as shown below:

7.5 MILE
WASH
ORE
OPLS 1106
WPLS 17372

From which:

"XBO" chiseled on East edge of a rock outcrop bears S 77° E, 24.3 feet.

"XBO" chiseled on West side of rock outcrop bears S 26° E, 12.7 feet.

A 5/8" X 30" iron rebar yellow plastic cap stamped "OR PLS 1106, WA PLS 17372" bears N 68 1/2° W, 46.2 feet, with bearing object sign attached, set steel fence 1 foot from rebar with witness sign attached.

Set steel fence post 1 foot North of corner, with witness sign attached. Compass declination 18° East.

This form is in compliance with the intent of RCW 65.04.045 and prescribed by the Public Land Survey Office, Department of Natural Resources - 1/97.

16N327.5MILEORN

RECEIVED BY

Umatilla County Surveyor

Date 9-01

Rec'd By [Signature]

No. 01-11-B