



7-31-01

LAND CORNER RECORD

GRANTOR/SURVEYOR/PUBLIC OFFICER: This corner record correctly represents work performed by me or under my direction in conformance with the Survey Recording Act.

COMPANY OR AGENCY: William R. Wells Land Surveying

ADDRESS: P.O. Box 1696
357 NE Hwy. 11
Pendleton, OR 97801

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will. R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

*renews 8-30-02
7/31/01*

GRANTEE: PUBLIC

SEAL/SIGNATURE/DATE

LEGAL: TWP: 6N RGE: 33E CORNER CODE: J-7

ADDITIONAL IDENTIFIER: (BLM designation, street or plat names, block, lot, etc.)

NORTH 1/4 CORNER OF SECTION 17.

COUNTY: Walla Walla

OREGON PLANE COORDINATES: N: 858107.78 E: 8656734.40, (inf ORN 83/91)

ORDER:

CORNER INFORMATION: Discuss the history, evidence found, and perpetuation of the corner. Diagram the references; provide the date of work; and, if applicable, a reference to a map of record and/or the field book/page no. Use the back, if needed.

1. HISTORY:

Corner originally established by Daniel E. Major under Contract No. 72, dated May 5, 1863. Record states: Set quarter section corner post on side of ridge built mound dug trench & pits.

2. EVIDENCE FOUND:

Railroad tie fence corner with fences North and West, and field line East. Field and fence lines extend East from fence corner for several miles. A stone, with no visible marks, is located 2.5' North of railroad tie fence corner—stone looks disturbed.

3. PERPETUATION INFORMATION:

At a point Northwest of railroad tie fence corner set a 2 1/2" aluminum cap on a 2 1/2" x 30" aluminum pipe with cap 4" above ground level. Cap is marked as shown below:

T6N R33E
S8
1/4-----
S17
2001
PLS 17372

This form is in compliance with the intent of RCW 65.04.045 and prescribed by the Public Land Survey Office, Department of Natural Resources - 1/97.
V6N33J7ORN

RECEIVED BY
Umatilla County Surveyor
Date 9-01
Rec'd By [Signature]
No. 01-111-B