

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 07/25/08

CORNER DESIGNATION: J-9, The Northwest Corner of Section 16, Township 6 North, Range 36 East, W.M..

PREVIOUS RENEWALS/SURVEYS ETC: Corner originally established by Odell & Lewis under GLO Contract No. 110, dated February 7, 1865. Notes state: Set post Cor. for fractional Secs. 16 & 17. Drove charred stake; dug pits & raised mound, as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

S17 WA
S17|S16 OR
CC
2008
PLS 1106

MONUMENT SET: Reestablished corner position by single proportionate measure, on the parallel of latitude, between recovered State Line Mileposts 30.0 and 31.5. At the reestablished corner point, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe with cap buried 8" below gravel road surface, marked as shown in "Monument Marking Detail".

New accessories:

A 5/8" x 24" rebar with a red plastic cap marked "OR PLS 1106, WA PLS 17372", bears North 08° East, 18.7 feet.

A 5/8" x 24" rebar with a red plastic cap marked "OR PLS 1106, WA PLS 17372", bears North 67° East, 41.6 feet.

A 3/4" brass washer stamped "PLS 1106", on a power pole, 1' above ground level, bears North 71° West, 103.1 feet.

A 5/8" x 24" rebar with a red plastic cap marked "OR PLS 1106, WA PLS 17372", bears North 56° West, 37.6 feet.

Bearing object sign and witness sign are nailed to power pole accessory.

Attached bearing object signs to rebar accessories.

Rebars accessories are set in road bank on the North side of State Line Road (East-West).

LOCATION AND COMMENTS: Corner falls in centerline, +- of State Line Road (East-West).

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 858347.22

E = 8753537.32


FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East


Surveyor's Seal

Witnesses: Jason Wells, LSIT

\6N36J9



William R. Wells



Renews 6-30-10

09-10-C