

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 07/31/08

CORNER DESIGNATION: N-21, The Northeast Corner of Section 23, Township 6 North, Range 36 East, W.M..

PREVIOUS RENEWALS/SURVEYS ETC: Corner originally set by Odell & Lewis under GLO Contract No. 110, dated February 7, 1865. Notes state: Set post Cor. for Secs. 13, 14, 23 & 24. Drove charred stake; dug pits & raised mound, as per instructions.

Bartleson, in his Survey No. 99-282-B, reestablished this corner by double proportion and set a "BC, 15" deep". I calculated the search point, searched, but did not find the Bartleson monument.

MONUMENT AND ACCESSORIES FOUND: None. Falls in farmed field.

MONUMENT MARKING DETAIL:

T6N R36E
S14 | S13
S23 | S24
2008
PLS 1106

MONUMENT SET: For departure, I held the mean location of a North-South field line extending South from the Northeast Closing Corner of Section 14 to the North side of Cottonwood Creek Road, and extended it South to the corner point. For latitude, I calculated the record proportional latitude between the recovered East One-Quarter corner of Section 23 and the Northeast Closing Corner of Section 14, based on the Odell and Lewis record. At the reestablished corner point, set a 2 3/8" brass cap on a 1 1/4" x 24" galvanized iron pipe, with cap buried 24" below ground level and marked as shown in "Monument Marking Detail".

New accessories, (bearings are State Plane grid bearings):

A 5/8" by 24" rebar with a red plastic cap marked "OR PLS 1106, WA PLS 17372", bears South 84°33' West, 95.8 feet.

A 5/8" by 24" rebar with a red plastic cap marked "OR PLS 1106, WA PLS 17372", bears South 60°18' West, 96.6 feet.

A 5/8" by 24" rebar with a red plastic cap marked "OR PLS 1106, WA PLS 17372", bears South 42°59' West, 103.9 feet.

A 5/8" by 24" rebar with a red plastic cap marked "OR PLS 1106, WA PLS 17372", bears South 20°47' West, 116.8 feet.

All rebars have bearing object signs attached. Nailed witness sign to a brushy tree 20' high, bears North 78° West, 95 feet, more or less, from corner point.

LOCATION AND COMMENTS: Corner falls in fallow field, about 95 feet East of a shallow draw running Northwest and 600 feet, more or less, South of farm buildings.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 855331.54
E = 8769535.40

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

6N36N21



renews 6-30-10 09-10-C