

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 04/04/08

CORNER DESIGNATION: P-13, The East Quarter Corner of Section 21, Township 6 North, Range 36 East, W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Odell & Lewis under GLO Contract No. 110, dated February 7, 1865. Notes state: Set 1/4 Sec. post. Dug pits & raised mound, as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. Falls in wheat field, no nearby features.

MONUMENT MARKING DETAIL:

T6N R36E
1/4
S21 | S22
2008
PLS 1106

MONUMENT SET: Corner point was reestablished by single proportionate measure between the accepted Southeast Corner of Section 21 and the accepted Northeast Corner of Section 21. At the reestablished corner point, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe with cap buried 18" below ground level, marked as shown in "Monument Marking Detail".

New accessories:

- A silver deep-1 magnet bears North 51° East, 36.2 feet.
 - A purple deep-1 magnet bears South 48 1/2° East, 35.0 feet.
 - A blue deep-1 magnet bears South 54 1/2° West, 25.5 feet.
 - An orange deep-1 magnet bears North 37 1/2° West, 27.9 feet.
- All deep-1 magnets are buried 20 inches below ground level with bearing object signs.

LOCATION AND COMMENTS: Corner falls in chemical fallow field, with no features.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 852267.62
E = 8758960.54

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

√6N36P13

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Expires 6-30-10

09-10-08