

OREGON CORNER RESTORATION FORM

COUNTY: Washington **DATE:** 06/18/2014

CORNER DESIGNATION: K-9 WA, Township 6 North, Range 37E, W.M.

PREVIOUS RENEWALS/SURVEYS ETC:

Walla Walla County Survey Bk. U, Pg. 172 Shows a rock 7" x 7" x 18" firmly set in the ground marking the line between sections 16 and 17, Washington.

Described by BLM Cadastral Surveyor Alfred White in the notes of his 1965 retracement.

MOUNUMENT AND ACCESSORIES FOUND:

Found a 7" x 7" x 18" rock with chiseled "X" on top and wrapped in pink flagging, firmly planted. The rock is approximately 5' south of a fence corner of West-North barbed wire fence. A 32" diam. Douglas fir with mostly healed blaze and a couple of illegible scribe marks, bears S 36° E., 18.00 ft.

MOUNUMENT MARKING DETAIL:

MOUNUMENT AND ACCESSORIES SET:

No new monument or accessories set at this time.

LOCATION AND COMMENTS:

Corner is on a gentle north slope amongst young scattered fir trees. Bearings taken with Silva hand compass and distances measured with a steel tape.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 859231.52
E = 8786456.22

COMPASS DECLINATION: 15° East


SURVEYORS' SEAL:

FIRM: HDJ Design Group
5 N. Colville, Suite 200
Walla Walla WA 99362

WITNESSES: Thomas J. Boshart
Felipe G. Hernandez



Greg E. Flowers



RENEWS 12/31/15

6/29/2015