

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 07/21/2014

CORNER DESIGNATION: N-23, Quarter Corner Section for Sections 13 and 24, Township 6 North, Range 37E, W.M.

PREVIOUS RENEWALS/SURVEYS ETC:

Originally surveyed by George Williams in 1872 his notes state "Set post for 1/4 section from which"

A fir 6 ins. diam., bears N. 14° E., 20 lks. dist.

A fir 12 ins. diam., bears S. 20° W., 8 lks. dist."

MOUNUMENT AND ACCESSORIES FOUND:

No Evidence Found

MOUNUMENT MARKING DETAIL:

 T6N
1/4 S13 R37E
 S24
 2014
 LS 02820

MOUNUMENT AND ACCESSORIES SET:

At the surveyed position, set a 1½" galvanized iron pipe with a 2½" brass cap. The cap stands 12" above ground on an East facing brushy slope, built mound 36" diam. x 12" high, around monument, from which:

A 9 ins. in diam., Douglas fir, bears N. 55½° W., 25.90 ft., blazed, scribed and tagged.

A 24 ins. in diam., Douglas fir, bears N. 14° E., 16.50 ft., blazed, scribed and tagged.

Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears S48½°W, 19.40 ft.

A 10 ins. in diam., Douglas fir, bears S. 56° E., 16.10 ft., blazed, scribed and tagged.

LOCATION AND COMMENTS:

Bearings taken with Silva hand compass and distances measured with a steel tape.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 856500.42

E = 8803567.28

COMPASS DECLINATION: 15° East

SURVEYORS' SEAL:

FIRM: HDJ Design Group
 5 N. Colville, Suite 200
 Walla Walla WA 99362

WITNESSES: Mark F. Wendover
 Felipe G. Hernandez

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Greg E. Flowers
OREGON
JUNE 30, 1997
GREG E. FLOWERS
02820LS

RENEWS 12/31/15

06/29/2015