

LOCATION AND COMMENTS:

Corner falls in wheat field near edge of bank, down to creek. Bearings taken with Silva hand compass and distances measured with a steel tape.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 855621.91

E = 8780208.73

COMPASS DECLINATION: 15° East


SURVEYORS' SEAL:

FIRM: HDJ Design Group
5 N. Colville, Suite 200
Walla Walla WA 99362

WITNESSES: Thomas J. Boshart
Felipe G. Hernandez
Joseph R. Latimer
Cory A. West



Greg E. Flowers



RENEWS 12/31/15

06/29/2015

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 1/13/2015

CORNER DESIGNATION: N-5, Corner of Sections 17, 18, 19 and 20, Township 6 North, Range 37E, W.M.

PREVIOUS RENEWALS/SURVEYS ETC:

Originally surveyed by A. H. Simmons for US Deputy Surveyor George Williams under his contract No. 176 dated July 20, 1872. His notes state "Set stone 8 x 16 x 20, for the Cor. to Secs. 17, 18, 19 and 20."

Surveyor Paul W.P. Tomkins noted in his April 9, 2001 survey, shown on Umatilla County Survey record of surveys 01-64-B, "Set 5/8" rebar with 2" aluminum cap 18" deep in field from topographic calls contained in G.L.O. notes. As called in said notes, we set the corner .6 chains (39.6') South of a 15' high bank, said point being 20' South of the current field edge, where we set a post and sign. 2.0 chains (132') west of rebar is a deep gully with a little water flowing as called in the G.L.O. notes. A fence corner to the South, West, and East is at the bottom of the bank 58.5 ft. north of our corner. We found an 8"x16"x20" stone, which we believe may have been the original stone also lying at the bottom of the bank. We set a post and bearing object sign at the stone; it bears N. 43°40' W., 133.47' from the corner."

Surveyor Paul W.P. Tomkins noted in his January 8, 2005 survey, shown on Umatilla County Survey Record of Plats 2005-02, "Rebar with aluminum cap at NW Corner Section 20, as shown on Survey 01-064-B."

Surveyor Paul W.P. Tomkins noted in his October 14, 2008 survey, shown on Umatilla County Survey Record of Plats 2008-29, "Rebar with aluminum cap at NW Corner Sec. 20, per Survey 01-064-B."

MOUNUMENT AND ACCESSORIES FOUND:

A 2 ins. aluminum cap on 5/8 ins. rebar, 14 ins. below ground surface, stamped for Corner of Sections 17, 18, 19 and 20, Township 6 North, Range 37E. T-post with bearing tag bears N 5° E, 20.9 ft.

MOUNUMENT MARKING DETAIL:

LS 02820
T 6N
S 18 S 17
S 19 S 20
R 37E
1/2015

MOUNUMENT AND ACCESSORIES SET:

At the position of the found rebar and aluminum cap, set a 2½ ins. brass cap on a 1½ in. galvanized iron pipe, 24.00 ins. below ground, in a plowed field from which:
Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears N. 42° W., 31.50 ft.
Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears N. 42° E., 22.00 ft.
Buried a "Deep-1" pink magnet, 18 ins. deep, with bearing tag, bears S. 42° E., 15.00 ft.
Buried a "Deep-1" blue magnet 18 ins. deep, with bearing tag, bears S. 45° W., 15.00 ft.