

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla **DATE:** 0/15/2015

CORNER DESIGNATION: N-7, Quarter Corner for Sections 17 and 20, Township 6 North, Range 37E, W.M.

PREVIOUS RENEWALS/SURVEYS ETC:

Originally surveyed by A. H. Simmons for US Deputy Surveyor George Williams under his contract No. 176 dated July 20, 1872. His notes state "Set stone 6 x 8 x 12 mound of stone for 1/4 Sec. Cor.

MOUNUMENT AND ACCESSORIES FOUND:

No evidence found.

MOUNUMENT MARKING DETAIL:

LS 02820
T 6N R 37E
 $\frac{S 17}{S 20} \frac{1}{4}$
1/2015

MOUNUMENT AND ACCESSORIES SET:

At the surveyed position, set a 2½ ins, brass cap on a 1½ x 30 ins. galvanized iron pipe in plowed field from which:

- Deposited an orange "Deep-1" magnet marker with bearing tag, bears N. 43° W., 10.00 ft.
- Deposited a silver "Deep-1" magnet marker with bearing tag, bears N. 61° E., 15.00 ft.
- Deposited a pink "Deep-1" magnet marker with bearing tag, bears S. 43° E., 12.00 ft.
- Deposited a blue "Deep-1" magnet marker with bearing tag, bears S. 54° W., 10.00 ft.

LOCATION AND COMMENTS:

Bearings taken with Silva hand compass and distances measured with a steel tape.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 855710.65
E = 8782812.62

COMPASS DECLINATION: 15° East

SURVEYORS' SEAL:

FIRM: HDJ Design Group
5 N. Colville, Suite 200
Walla Walla WA 99362

WITNESSES: Joseph R. Latimer
Cory A. West

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Greg E. Flowers
OREGON
JUNE 30, 1997
GREG E. FLOWERS
02820LS

RENEWS 12/31/15

06/24/2015